

Job: Salzer, Doug

**ESTIMATE**

**X**



Date:

Friday, June 26, 2009

Estimate Valid for 60-days

<b>Site Excavation &amp; Waste Removal :</b>	\$300.00
<b>Aggregate</b> (>30 tons)	\$550.00
<b>Retainig Wall:</b>	
Anchor Diamond Straight (Rock Blend or Sandstone)	
Anchor Wall Caps	
	\$2,623.00
<b>Freight &amp; Fuel Surcharge:</b>	\$500.00
<b>Machinery &amp; Labor:</b> (Skid Steer & Compactor)	\$3,402.00
	\$7,375.00
<b>Re-Route Drainage below-grade</b>	\$125.00
Project Length: 3-5 days	
<b>Total</b>	<b>\$7,500.00</b>

**SCOPE & DESIGN NOTES:**

Anything higher than 4' shall require an Engineers Design

Adequate sub-grade course is included

Wall stone specifications: 17 1/4" L x 12" W x 6" H, 72 lbs each

Landscape fabric shall be installed to serves as a filter keeping small soil particles from working their way through the wall when moisture presents itself.

Wall Caps shall be adequate fastened with construction grade adhesive

(Wall may be modified at a later date with some minor variation in batch & color type.)

Estimate does not take into account any unforeseen obstables, rock material or debris that may un-earthed, uncovered or displaced.

Any additional costs and Change-Orders shall be the joint responsibility of Home Owner & Contractor.

Adding Value shall not be held responsible for distrssed sod or turf caused

by reasonable & customary contact with heavy equipment or scope of work.

Adding Value provides and supports Manufacturers 5-year Product Warranty

